

PRE-ASSEMBLED VIEW
(WITHOUT TOP PLATES)

PANEL SCREWS
W/ WASHERS AT
24" O.C. (U.N.O.)

OPTIONAL
FACTORY
INSTALLED
ELECTRICAL
CHASE

CONTINUOUS $\frac{3}{8}$ " & $\frac{1}{2}$ "
PREMIER MASTIC ON
EACH SIDE OF LUMBER
ON EACH PANEL

#8x1 $\frac{1}{2}$ " SCREWS @
8" O.C. OR 8d NAILS
@ 6" O.C. BOTH
SIDES, TOP AND
BOTTOM (U.N.O.)

EXTREME WALL
PANEL

$\frac{7}{16}$ " OSB SKINS ON
BOTH SIDES, TYPICAL

EXPANDED
POLYSTYRENE CORE

ASSEMBLED VIEW

TOP PLATES

NAIL OR SCREW THE
TOP PLATE TO THE
VERTICAL STUD WITH
(3) 16d NAILS OR
(3) #9x3" SCREWS

PRE-DRILL TOP AND
SILL PLATES AT
ELECTRICAL CHASE
LOCATIONS BEFORE
PLATES ARE INSTALLED

SECTION
NOT TO SCALE

DETAIL TITLE : BUTT CORNER CONNECTION (STD)

DETAIL NO. : EP-112

PAGE NO. : 1 - 12

UPDATED : 2/5/2009

Extreme Panel
Technologies, Inc.
QUALITY EFFICIENT BUILDING SYSTEMS